

27-16-10w


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE ATLANTIC REFINING CO.
Stoltenberg "A" No. 4

SEC. 27 T. 16 R. 10W.
CN $\frac{1}{2}$ SE SE

Total Depth. 3301.
Comm. 11-8-40 Comp. 12-3-40
Shot or Treated.
Contractor.
Issued. 1-18-41

County Ellsworth.



	Rotary	3293
CASING.	Cable	3301

85/8" 366'
5 1/2" 3289'

Elevation.

Production. Pot. 2020B.
Depthograph.

Figures Indicate Bottom of Formations.

surface clay and sand	95	Arbuckle	3289-3301
shale	140		
sand	194		
red bed	264		
shale and shells	371		
shale and sand	450		
red bed and shale	590		
anhydrite	621		
shale and shells	960		
shale	1050		
salt	1190		
shale	1335		
anhydrite	1385		
lime and shale	1470		
shale	1505		
lime	1530		
broken lime	1680		
lime	1750		
lime broken	2030		
lime and shale	2135		
shale and shells	2375		
lime ..	2450		
shale	2525		
broken lime	2650		
lime	2707		
lime broken	2785		
lime	2915		
shale	2930		
lime and shale	3075		
lime broken	3135		
lime	3288		
Cored 3288 - 3294			
lime	3301		

Total Depth.

11-26-40 Acidized with 1000 gal - jet gun.
11-27-40 Acidized with 1500 gal.