

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.


07.7.1941  
27-16-10W  
Plotted by T. S. CO. 1

ATLANTIC REFINING CO.  
Stoltenberg No. 2-E

SEC. 27 T. 16 R. 10W.  
CS $\frac{1}{2}$  NW SE

Total Depth. 3296  
Comm. 7-18-40 Comp. 8-14-40  
Shot or Treated. 8 qts 3294-3288 8-7-40  
Contractor. Taber and Coleman.  
Issued. 8-31-40

County Ellsworth.



Rotary with cable tool  
Completion.

CASING.

85/8" 365'  
5 1/2" 3284'6"

Elevation.

Production. Pot. 1436 B.

Figures Indicate Bottom of Formations. Depthograph.

surface (11" Hole)	100	bottom line	2585
shells shale red bed sand	378	shale	2597
shale grey	450	lime broken	2674
red bed	580	lime	2845
anhydrite	605	broken lime	2910
shale and shells	730	shale	2953
red bed and shale	990	slate	2955
red bed and shells	1020	lime and slate	2990
salt	1220	lime	3296
shale and shells	1270	Total Depth.	
shale	1285		
broken lime	1335		
lime white	1357	Top of Arbuckle	3284
shale	1373		
anhydrite	1390		
shale	1405	8-5-40	3284'6" - 3294 2000 gal
lime - solid	1473	8-11-40	3284'6" - 3296 2000 gal
broken lime	1500	8-12-40	3284'6" - 3296 1500 gal.
lime	1525		
red bed and shells	1560		
broken lime	1600	Coring record. 3284-3287	Rec. 35"
sdv lime	1628		very dense lime with slight sat.
sand grey	1653		
sdv lime	1676		
lime	1690		
shale and lime shells	1780		
shale and shells	1796		
sand	1810		
lime	1847		
shale and lime shells	2025		
lime shale and shells	2140		
shale and shells	2360		
shale and lime	2375		
lime	2420		
shale and lime	2430		
shale	2505		