

27-16-10W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ATLANTIC REFG. CO.
Farm - Stoltenberg "E" No. 6

SEC. 27 T. 16 R. 10W
SW SE SW SE
75' NSL & 760' EWL W $\frac{1}{2}$ SE $\frac{1}{4}$

Total Depth. 1170'
Comm. 10-27-47 Comp. 12-4-47 (Shut Down)
Shot or Treated.
Contractor. Campbell Drlg. Co.
Issued. 2-19-49

County. Ellsworth
KANSAS



Elevation. _____

Production. S.W.D.W.

CASING:

10-3/4" 359' Cem. w/175 sx.

Figures Indicate Bottom of Formations.

clay & shale	45
shale & shells	350
clay & shells	360
shale & shells	525
red bed	565
anhydrite	600
red bed & shale	685
no returns	1170
Total Depth	

Lost circ. at 1110'. Pumped in
500 sx. cem. mixed w/3% Howcogel
& 500# gel flakes. Drilled cem.
to 920'. Lost returns at 675'
Re-cemented from bottom up with
500 sx. cem. w/10% gel. Drilled
cem. Lost circ. at 980' - Started
losing at 740'. Re-cemented w/400
sx. In drilling out found no cement
until 675'. lost circ. at 985'.

Moved out tools Dec. 4, 1947.