


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

27-16-10W

Company - THE ATLANTIC REFINING CO.
 Farm Stoltenberg "E" No. 7

SEC. 27 T. 16 R. 10W
 C SW/4 SE
 652' N of S1 & 660' E
 of WL of W/2 SE/4
 County. Ellsworth
 KANSAS

Total Depth. 3840'
 Comm. 8-7-48 Comp. 9-3-48
 Shot or Treated. Acidized w/8,000 gals.
 Contractor. South Oak Drilling Co.
 Issued. 10-2-48



CASING:

13 3/8" 310' Cem w/250 Sx. & 200# CC
 7" 3449' Cem w/700 Sx. & 400# CC

Elevation. 1815' and

Production. S.M.D.M.

Figures indicate Bottom of Formations.

shale	30
shale and sand	190
shale and shells	460
redbed and shale	580
anhydrite	605
shale and shells	1320
lime and iron	1343
lime and shale	1435
shale and shells	1570
shale, sdy	1600
lime and shale	1665
lime	1845
lime and shale	2255
shale and shells	2635
lime	2850
lime, brkn	2985
lime	3769
sand	3800
sand, sharp	3823
granite	3840
total depth	

Tops:

Arbuckle 3277'

DST 3339-3356 Recovered
 700 feet, salt water
 Acidized w/8000 gals.

Tested water input rate
 108 bbls. in 13 minutes-
 480 bbls water pre hr.