

27-16-1000


STANOLIND OIL AND GAS CO.
John H. Stoltenberg "F" No. 3

SEC. 27 T. 16 R. 10W.
CS $\frac{1}{2}$ SW NW
330' N SL 660' E WL NW $\frac{1}{4}$

Total Depth. 3298
Comm. 10-14-40 Comp. 11-3-40
Shot or Treated.
Contractor.
Issued. 12-21-40

County Ellsworth.

CASING. Rotary 3296
Cable 3298



85/8" 251'8"
5 1/2" 3288'3"

Elevation.

Production. Pot. 964 B.

Figures Indicate Bottom of Formations. no wtr. Draw down

cellar	7.91
clay	80
clay and sand	100
shale and shells	480
shale red rock	608
anhydrite	640
shale and shells	1030
shale	1055
salt and shale	1320
broken lime	1390
lime	1450
broken lime	1540
shale	1570
broken lime sdy	1600
broken lime	1670
sdv lime	1696
broken lime	1890
lime	1932
broken lime	2120
shale	2390
lime	2400
broken lime	2445
shale	2550
broken lime	2635
lime	2850
broken lime	2935
shale	2990
broken lime	2995
lime	3090
broken lime	3110
lime	3245
lime brkn	3287
dolomite	3298
Total Depth.	
Arbuckle lime	3287-3298