

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas

Plotted *gwr*


27-16-10W

STANOLIND OIL AND GAS CO.
J.H. Stoltenberg "D" No. 4

SEC. 27 T. 16 R. 10W.
CN $\frac{1}{2}$ SW NE
990' N SL 660' E WL NE $\frac{1}{4}$

Total Depth. 3319 P.B. 3311
Corm. 8-25-40 Comp. 9-21-40
Shot or Treated.
Contractor.
Issued. 11-9-40

County Ellsworth.



CASING.

ROTARY 3302
Cable 3319 PB 3311

85/8" 260'4"
5 1/2" 3299'2"

Elevation.

Production. Pot. 283 B.
16 BW.

Figures Indicate Bottom of Formations.

cellar	8.17
shale grey	450
red bed	515
shale red rock	585
anhydrite	615
shale	775
red rock and shale	1080
salt and shale	1240
shale lime shells	1370
shale gyp	1400
shale	1450
shale and shells	1514
shale	1693
shale and shells	1900
shale	2520
broken lime and shale	2550
lime	2583
broken lime	2647
lime	2700
shale	2748
lime shale breaks	2830
lime	2872
shale	2905
lime	2919
shale	2970
lime	2980
lime and shale	3005
lime	3057
lime and shale	3080
shale	3105
lime	3281
correction 3281 equals	3273
lime	3292
shale	3297
sand	3298
lime	3319
Total Depth	P.B. 3311

Top of Arbuckle 3298

Physical Potential pumped 94 bbls oil and 5 bbls water in 8 hours through 2" tubing with the pump running 30-36" SPM to establish a potential of 283 bbls oil and 16 bbls water.

cement from 3311 to 3319. Water shut off from 3 bbls wtr per hour to 3 gallons water per hour.