

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Plotted


27-16-10W

ATLANTIC REFG. CO.
Stoltenberg No. 1-E.

SEC. 27 T. 16 R. 10W
CN $\frac{1}{2}$ NW SE

Total Depth. 3276'
Comm. 2-28-40 Comp. 3-18-40
Shot or Treated. No.
Contractor. Taber & Coleman
Issued. 4-6-40 Rotary tools w/
cable tool completion

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 370'
5 $\frac{1}{2}$ " 3271'6"

Elevation.

Production. Pot. 24,903 B.
Depthograph

Figures Indicate Bottom of Formations.

red bed & shale	170
shale, shells, sand	335
shale & shells	380
shale	450
shale & red bed	570
anhydrite	610
shale & red bed	705
shale & shells	815
red bed, shale, shells	970
shale & shells	1040
shale & salt	1310
lime	1330
shale & lime	1365
lime	1420
shale & lime	1440
lime	1530
shale	1545
lime	1645
shale	1660
lime	1750
shale	1765
lime	1870
shale & lime	1890
lime	1910
shale	1940
lime	1960
shale	2010
shale & lime	2090
shale & shell	2175
shale	2275
shale & lime	2460
shale	2500
shale & lime	2575
shale	2590
lime	2620
shale & lime	2635
lime	2900
shale & lime	2950
lime	3170
shale & lime	3249
lime	3276
Total Depth.	

Top Kansas City 2948
Top Arbuckle 3272

Cored 3273-76 full recovery
good porosity & saturation

When the plug was drilled out, the
hole filled up 3000' w/oil in 25
min., w/bridge in hole. Had
to drill 1 $\frac{1}{2}$ hrs to go thru bridge.
After cleaning out to btm & swabbing
down 1000', started to test. The
well made 93 B. in 1 hr 1000' from
the top of the hole.

Not shot or acidized