

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

FM.


27-16-10W

ATLANTIC REFG. CO.
Stoltenberg "E" No. 3.

SEC.27 T.16 R.10W
CS $\frac{1}{2}$ SW SE

Total Depth. 3288'
Comm. 10-10-40 Comp. 11-5-40
Shot or Treated.
Contractor. Taber & Coleman
Issued. 12-14-40

County. Ellsworth



Rotary w/cable
tool completion

CASING:
8 5/8" 356'
5 1/2" 3280'

Elevation.

Production. Pot. 393 B.

Figures Indicate Bottom of Formations.

surface clay & shells	70
red bed	110
sand	175
shale & shells	225
red bed & shells	300
shale & shells	350
gravel	370
shale	450
red bed shale	560
anhydrite	585
shale, shell	1005
salt	1235
shale & shells	1310
lime	1410
lime brkn	1520
shale & lime	1715
lime brkn	1880
shale & lime	2090
brkn lime & shale	2195
lime	2215
shale	2280
shale & lime	2300
shale	2350
lime	2380
shale	2420
lime brkn	2440
shale & lime	2500
lime	2865
shale & lime	2935
shale	2943
lime	2970
shale & lime	2990
lime	3288
Total Depth.	

Top Arbuckle 3279

Acidizing Record:
10-27-40 Halliburton Jet 1000 Gals.
10-28-40 15% N.E. 1000 Gals.
10-30-40 15% N.E. 1000 Gals.
11- 2-40 4000 Gals.