

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


27-16-10W

ATLANTIC REFG. CO.
Stoltenberg "E" No. 5.

SEC. 27 T. 16 R. 10 W
SW SE SW SE
180' N SL 760' E WL W $\frac{1}{2}$ SE $\frac{1}{4}$

Total Depth. 3866'
Comm. 6-12-43 Comp. 7-7-43
Shot or Treated. 7-7-43 5000 Gals. Acid
Contractor. Parker Drlg. Co.
Issued. 7-24-43

County. Ellsworth



CASING:
10 $\frac{3}{4}$ " 678' Cem.
7" 3746' Cem.

Elevation.

Production. Salt Wtr Disp

Figures Indicate Bottom of Formations.

surface hole	0-75	
gravel & shale	420	300 gallons per minute
shale & shells	500	
red bed	570	
anhydrite	658	
shale	678	
shale & shells	1250	
salt & shale	1290	
shale & shells	1440	
brkn lime & shale	1555	
sdv lime & shale	1695	
lime & shale	1800	
lime	1900	
lime & shale	2080	
shale & shells	2195	
lime & shale	2459	
shale	2500	
lime	2550	
lime & shale	2718	
lime	2915	
shale & lime	2950	
lime	3248	
shale & lime	3257	
lime brkn & shale	3370	
conglomerate	3419	
lime	3430	
lime cherty	3440	
lime	3484	
lime brkn	3523	
lime	3606	
lime sdv & shale	3617	
lime & shale	3694	
lime	3828	
sand & lime	3832	
lime	3834	
sand & lime	3842	
granite	3866	
Total Depth.		

Area below 3746 acidized w/
5000 Gals. Input of wtr