

DRILLER'S WELL LOG

27-16-10W
State Geological Survey
WICHITA BRANCH

JAN 22 1982

DATE COMMENCED: 11-01-80
DATE COMPLETED: 11-06-80

Petro, Inc.
Zvolanek No. 1
100' W of NW SE SW Sec. 27-16s-10w
Ellsworth County, Kansas

ELEVATION: 1834' K.B.
1829' G.L.

FORMATION DATA

597' Anhydrite
2852 - 2857' Shale
2857 - 2874' Lime
2874 - 2887' Lime
2887 - 2957' Lime & Shale
2957 - 2970' Lime & Shale
2970 - 3252' Lime
3252 - 3274' Lime & Shale
3274 - 3284' Dolomite
3284' RTD

Anhydrite 597'
Heebner 2852'
Toronto 2874'
Douglas 2887'
Brown Lime 2957'
Lansing K.C. 2970'
Base K.C. 3252'
Arbuckle 3274'
RTD 3284'

SURFACE PIPE:

Ran 9 jts. of 24# used 8 5/8".
Tally 358.28'. Set @ 365' with
200 sks. of Common Cement, 2% Gel,
3% c.c. Cement did circulate.
By Allied Cementing.

PRODUCTION PIPE:

Ran 83 jts. of 14# 5 1/2". Tally
3285.95'. Set @ 3279', 5' off
bottom, w/100 sks. Common, 10%
salt. By Sun Cementing. P.D.
12:30 p.m. on 11-6-80.

REC - 21310
CONSERVATION DIVISION
WICHITA, KANSAS

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

LARRY CURTIS, of lawful age, does swear and state that the facts
and statements herein contained are true and correct to the best of his
knowledge.