

28-16-10W

State Geological Survey
WICHITA BRANCH
DRILLER'S WELL LOG

DATE COMMENCED: 07/13/81
DATE COMPLETED: 07/17/81

Allen Drilling Company
SCHROEDER Well No. 1
SW SW NW
Sec. 28, Twp. 16S, Rge. 10W,
Ellsworth County, Kansas

ELEVATION: G.L.
K.B.

FORMATION DATA:

No geologist, no tops

SURFACE PIPE:

Ran 8 jts 28# used 8-5/8"
casing; tally: 328.07'
Set @ 335' w/ 225 sks 50/50
poz., 2% gel, 3% c.c.,
cement circ., plug down
@ 5:15 AM, 7/14/81
By Howco

PRODUCTION PIPE:

Ran 82 jts. 10.5# 4 1/2"
casing; tally: 3413.81';
Set @ 3372' w/ 150 sks
50/50 poz., 18% salt, 3/4%
CFR2, plug down 10:15 PM,
7/17/81, By Howco

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)

ss.