

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


28-16-104
Plotted

STANOLIND OIL & GAS CO.
Genhart Schroeder No. 1.

SEC. 28 T. 16 R. 10W.
CEL NE NE
1980' N of S.L. 2310' E of WL NE $\frac{1}{4}$

Total Depth. 3316.
Comm. 1-29-40 Comp. 2-24-40
Shot or Treated. 3500 acid and 10 qts.
Contractor.
Issued. 3-30-40

County Ellsworth.



CASING.		Rotary	3310
		Cable	3316
85/8"	257' 1"		
5 1/2"	3290 1/2'		

Elevation.

Production. Pot. 457 B.

Figures Indicate Bottom of Formations.

surface clay	25
lime shells	35
shell	250
shale and shells	257
shale	337
shale shells and red rock	582
red rock	614
anhydrite	635
shale	651
lime	685
shale and shells	862
shale	1085
shale and salt	1285
anhydrite shale	1450
lime broken	1520
lime and shale	1600
lime broken	1665
shale	1700
lime broken	1760
lime and shale	1815
lime broken	2140
shale lime shells	2255
lime broken	2495
shale and shells	2626
lime	2860
shale and lime	2925
shale	2982
lime	2985
Top Lansing 2986 Derrick floor.	
shale lime	2998
lime	3029
lime porous	3031
lime	3135
lime broken	3180
lime	3300
Top Arbuckle 3298 Derrick Floor.	
dolomite	3316

Top Lansing lime 2986 Derrick Floor.
Arbuckle lime 3298-3316
1 1/2" BPH Natural 16BPH after acidizing with 3500 gal and shooting with 10 qts.

Total Depth.