

30-16-10w

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**808 EAST MURDOCK - WICHITA, KANSAS**

COMPANY **MESSMAN-RINEHART OIL**

SEC. 30 T. 16 R. 10W  
 LOC. SE NW SE

FARM **Schlessinger "A"** NO. 2

COUNTY **Ellsworth**  
 KANSAS

TOTAL DEPTH **3366**


COMM. **8-28-67**

COMP. **9-7-67**

SHOT OR TREATED

CONTRACTOR **Gabbert-Jones**

ISSUED **5-18-68**



CASING

20	10	
15	8	5/8" @ 319' w/150 SX
12	6	
13	5	

ELEVATION **1883'KB**

PRODUCTION **25 BOPD**  
 ARB **3354-66**

FIGURES INDICATE BOTTOM OF FORMATIONS

FROM	TO	FORMATION	NOTES
0	70	SURFACE SOIL AND SAND	
70	155	SHALE	
155	185	SAND	
185	270	SHALE	
270	280	SAND	
280	319	SHALE	RAN 16 JOINTS 8-5/8" CASING, SET @ 319' w/150 SACKS CEMENT.
319	667	SHALE AND RED BED	
667	688	ANHYDRITE	
688	800	SHALE	TOPS: SAMPLE
800	1575	SHALE AND SHELLS	Heebner 2900
1575	1810	SHALE AND LIME	Brown Lime 3001
1810	2310	LIME	L/Kansas City 3015
2310	2710	LIME AND SHALE	Arbuckle 3348
2710	2990	LIME	
2990	3043	LIME AND SHALE	
3043	3349	LIME	
3349	3366	ARBUCKLE	
3366	TD		RAN 104 JOINTS 5 1/2" CASING, SET @ 3354' w/100 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE SE NW SE SECTION 30-163-10W, ELLSWORTH COUNTY, KANSAS TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*  
 \_\_\_\_\_  
 E. E. HALL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY