

30-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - A-B-W DRILLING CO., INC.
Farm - Zajic No. 1

SEC. 30 T. 16 R. 10W
SW SW SW

Total Depth. 3370½
Comm. 6-17-49 Comp. 6-26-49
Shot or Treated.
Contractor.
Issued. 8-6-49

County. Ellsworth
KANSAS



CASING:
8 5/8" 192' cem w/100 sx.
5 1/2" 3342' cem w/75 sx.

Elevation. 1872 ~~ft~~

Production. Dry Dry

Figures Indicate Bottom of Formations.

surface clay	65
shale, shells	685
anhydrite	720
shale	815
red bed	855
shale, shells	1150
salt	1300
shale	1335
shale, shells	1400
lime, shale	1520
shale, shells	1720
lime, shale	2160
shale, shells	2430
lime, shale	3015
lime	3325
conglomerate	3341
Arbuckle lime RTD	3348
Arbuckle hrd	3350
Arbuckle, not so hard	3351½
Arbuckle, very hrd, slight trace oil	3357
Arbuckle hrd, nothing in it	3362
Arbuckle 11G0, 9GW	3364
Arbuckle hrd, no Inc.	3368½
Arbuckle 4BW, 9G0	3370½
Total Depth	