


ATLANTIC, SHARON DRIG.CO.INC, ET AL
Novotry No. 1.

32-16-10W
SEC. 32 T.16 R.10W
CNL NW NE

Total Depth. 3318 $\frac{1}{2}$ '
Comm. 4-19-40 Comp. 6-1-40
Shot or Treated. 3000 Gals., 12 Qts.
Contractor. Sharon Drig.Co,Inc.
Issued. 6-22-40

County. Ellsworth



CASING:
8" 140'
5" 3294'

Elevation.

Production. Dry & Abnd.

Figures Indicate Bottom of Formations.

clay	28	Top Ft.Riley 1570
sand	35	Top Florence Flint 1690
clay & shells	164	Top Topeka 2620
clay	250	Dodge 2967-80
shale	375	Top Lansing 2989
shale & shells	475	Top Conglomerate 3289
red rock	600	Top Arbuckle 3292
anhydrite	635	
red rock	675	
shale	1080	
shale & salt	1290	
shale & shells	1340	
lime	1400	
shale	1440	
shale & shells	1840	
sand	1660	
shale	1675	
sand	1710	
lime	1740	
shale	1805	
shale & lime	1920	
lime	1940	
shale & shells	2005	
shale & lime	2030	
lime	2060	
shale & lime	2280	
shale	2330	
lime	2340	
shale	2420	
lime & shale	2465	
shale & shells	2530	
lime brkn	2550	
shale	2600	
shale & shells	2645	
lime brkn	2655	
lime	2880	
shale	2890	
lime	2930	
shale	2967	
lime	2985	
shale	2993	
lime	3013	
shale	3017	
lime	3173	
shale	3180	
lime	3255	
shale & lime	3294	
dolomite	3299	
cored 3299-3308 rec 7'		
dolomite dense	3303 $\frac{1}{2}$	
shale green	3305	
dolomite sft, sh oil	3308	
dolomite hrd	3318 $\frac{1}{2}$	
Total Depth.		

At 3318 $\frac{1}{2}$ had 5 gal.oil
1000 Acid(jet) from 3305-13
1 $\frac{1}{2}$ BOPH & trace wtr
shot 12 Qts.3302-12 no inc.
2000 Acid (jet)
Swab 9 B.fluid PH 80% sulphur wtr