

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

33-16-10W

Company - CITIES SERVICE  
Farm - Stoltenberg No. 2

SEC. 33 T. 16 R. 10W  
NE SE SE  
990' N & 330' W of SE Corner

Total Depth. 3290'  
Comm. 4-23-48 Comp. 5-10-48  
Shot or Treated. Acid. W/1000 gals. 5-13-48  
Contractor. Herndon Drlg. Co.  
Issued. 8-21-48

County. Ellsworth  
KANSAS



Elevation. 1825-Ind.

Production. Pump. 147 BO, no wtr.

CASING:

8-5/8" 365' Cem. W/150 Sx.  
5-1/2" 3279' Cem. W/150 Sx.

Figures Indicate Bottom of Formations.

shale & shells	365
clay & shale	495
red bed	580
anhydrite	610
shale & shells	900
salt & shale	1300
shale & lime	1325
lime & shale	1680
lime	1770
shale & lime	2495
lime	2620
lime & shale	2655
lime	3256
shale & lime	3280
2200 RTD = 3380 SLM	
lime	3290
Total Depth	

Tops:  
Lansing 2969  
Arbuckle 3276  
Penetration 14

2 1/2 FT in 1 1/4 hrs.  
175' oil in 1 hours  
750' oil in 8 hours