

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

33-16-10W

COMPANY CITIES SERVICE OIL CO.

SEC. 33 T. 16 R. 10W

FARM Stoltenberg "A" NO. 5


LOC. SW 1/4 SE

990' S & 330' E of center

TOTAL DEPTH 3286
 COMM. 9-3-50 COMP. 9-16-50
 SHOT OR TREATED Acid 1000 gals.
 CONTRACTOR Barbour Drllg Co.
 ISSUED 12-16-50

COUNTY Ellsworth

KANSAS



CASING

8 5/8" 305' cem w/150 sx.
 5 1/2" 3276' cem w/150 sx.

ELEVATION 1833

PRODUCTION Pmp 95 bbls oil
 / NW

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil, sand,
 clay 40
 shale, shells 225
 red bed, shells 306
 shale 460
 red bed, shale 590
 anhydrite 625
 shale, shells 1023
 salt, shale 1260
 shale, lime 1455
 lime, shale 1560
 shale, lime sandy 1685
 lime 1860
 lime, shale 2085
 shale 2575
 lime, shale 2635
 lime 2730
 shale, lime 2820
 lime 2955
 lime, shale 2980
 lime 3050
 lime, shale 3133
 lime 3248
 lime, shale 3277
 lime RTD 3282
 3282 RTD = 3276 SLM
 lime 3286
 Total Depth

Tops: Corr.

Lansing 2966
 Arbuckle 3275
 Penetration 11

Fillup: 130' oil in 45 mins.
 225' " " 1 hr 50 mins.
 960' " " 13-3/4 hrs.

Elevation 1830 Gr.