

33-16-10W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


Company - CITIES SERVICE OIL COMPANY
Farm - Stoltenberg "A" No. 3

SEC. 33 T. 16 R. 10W
NE NW SE
330' S & 990' E of Center

Total Depth. 3299
Comm. 4-7-50 Comp. 4-21-50
Shot or Treated. 1000 acid
Contractor. Lohmann-Johnson Drlg. Co., Inc.
Issued. 7-8-50

County. Ellsworth

KANSAS



Elevation. _____

Production. Pump. 103 oil,
trace wtr

CASING:
8 5/8" 265' cem. 175 sx
5 1/2" 3278' cem. 125 sx

Figures Indicate Bottom of Formations.

surface	80
shale	417
shale & shells	840
anhydrite	875
shale & shells	1470
broken lime	2125
shale & limo	2270
shale	2520
limo & shale	2667
limo	2872
shale & limo	2958
limo	2997
limo & shale	3054
limo	3279
3279 RTD = 3279 SIM	
limo	3299
Total depth	

Tops:	
Topoka	2738
Lansing	2982
Arbucklo	3278
Penetration	21'
Total depth	3299

Fill up 25' oil in 1 hr. @ 3293
350' oil in 8 hrs. @ 3299