


33-16-10W

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Stoltenberg "A" No. 6

SEC. 33 T. 16 R. 10W
SW SW SE
330 N, 330' E of
S/4 Corner
County. Ellsworth
KANSAS



Total Depth. 3306
Comm. 4-22-51 Comp. 5-29-51
Shot or Treated.
Contractor. J. W. Braden Drlg. Co.
Issued. 9-1-51

CASING:

8 5/8" 290' cem w/150 sxs.
5 1/2" 3270' cem w/150 sxs.

Elevation. 1830

Production. 362 oil pumped

Figures Indicate Bottom of Formations.

surface clay	45
shale, sand	200
shale, shells	297
shale, shells, red	
bed	700
shale, shells	1025
lime, shale	1555
broken lime	1720
lime, shale	1940
lime	2055
shale, lime	2595
lime	3276
3276 RTD = 3271 SLM	
lime	3306
Total depth	

Tops: Corr.	
Lansing	2960
Arbuckle	3269
Penetration	37

Fillup:

710' oil in 1 1/2 hrs. at 3306
1820' oil in 2 1/2 hrs. at 3306
2090' oil in 3 1/2 hrs. at 3306
2570' oil in 5 1/2 hrs. at 3306