


33-16-10W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Stoltenberg "A" No. 7

SEC. 33 T. 16 R. 10W
NW SW SE
990 N, 330 E of S/4
corner
County. Ellsworth
KANSAS



Total Depth. 3286'

Comm. 6-11-51

Comp. 7-5-51

Shot or Treated.

Contractor. J. W. Braden Drlg. Co.

Issued. 9-1-51

CASING:

8 5/8" 363' cem w/175 sxs.
5 1/2" 3269 cem w/150 sxs.

Elevation. 1830

Production. 133 BO pumped

Figures Indicate Bottom of Formations.

shale	260
shale, shells	1075
salt, lime	1125
shale, shells	1345
lime, shale	1700
lime	1965
shale, shells	2010
shale, lime	2750
lime	3000
lime, shale	3080
lime	3283
3283 RTD = 3277 SLM	
lime	3286
Total depth	

Tops: Corr.

Lansing 2949

Arbuckle 3266

Penetration 20

Fullup:

160' oil in 1 hr at 3286

1170' oil in 16 hrs. at 3286.