


MID CONTINENT PETRO. CORP.
B. Matosh No. 3

Plotted Texas CO.
SEC. 34 T. 16 R. 10W.
CNL NW NE
330'fNL 660'fWL NE $\frac{1}{4}$

Total Depth. 3295
Comm. 4-5-41 Comp. 5-5-41
Shot or Treated.
Contractor. Mac and Stauffer.
Issued. 6-14-41

County Ellsworth.



CASING.

103/4" 215'3" cemented.
7" 3282'6" cemented.

Elevation.

Production. Pot. 534 B.

Figures Indicate Bottom of Formations.

soil	10	
clay	50	
sand	80	
shale and shells	230	Arbucklo dolomite 3285
shale and shells	350	brokon green sdy limo 3288
shale	428	brokon green limo and pyrites 3289
red bed	520	broken lime green and brown 3291
sdv shale	630	broken reddishlime 3291 $\frac{1}{2}$
shale and sand	755	broken grey lime 3293
shale and shells	1030	arbuckle lime 3294
shale	1150	grey lime and green shale 3295
salt	1275	Total Depth.
lime and shale	1334	
broken lime	1445	
lime and iron✓	1550	
lime and shale	1650	
sdv limo	1670	
lime	1735	
lime and shale	1798	
lime	1890	
sticky shale	1980	
shale and shells	2260	
shale	2280	
limo	2300	
shale and limo	2540	
limo	2555	
shale and limo	2600	
lime	2630	
shale	2725	
lime	2880	
shale and shells	2953	
shale	2960	
KC limo	3173	
brokon limo	3230	
shale and shells	3257	
KC limo	3260	
conglomerate	3264	
shale	3268	
brokon limo	3271	
shale	3275	
brokon lime shale & pyrito	3282	
brokon limo and shale	3286	