

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


34-16-10W

ATLANTIC REFG.CO.
Matosh No. 1.

SEC.34 T.16 R.10W
CN $\frac{1}{2}$ NE SE

Total Depth. 3297=3293 SIM
Comm. 7-27-40 Comp. 8-28-40
Shot or Treated.
Contractor. Taber & Coleman
Issued. 9-21-40

County. Ellsworth



Rotary w/cable
tool completion

CASING:
10 $\frac{3}{4}$ " 345'
5 $\frac{1}{2}$ " 3278'

Elevation.

Production. Pot.186 B.Deptho.

Figures Indicate Bottom of Formations.

sand	40
surface	70
shells & red bed	150
shells & slate	250
shale & shells	350
red bed, sand-lime	590
anhydrite	615
red bed & shells	715
shale & shells	840
lime	860
shale & shells	990
salt	1045
shale & salt	1220
shale, lime, shells	1295
shale & shells	1315
anhydrite	1360
lime	1405
shale & lime	1505
shale, lime, sand	1565
shale & lime	1700
sand & lime	1715
shale & lime	1850
lime	1920
shale & shells	2080
shale & lime	2130
shale & shells	2370
lime brkn	2400
shale & shells	2465
shale & lime	2555
shale & shells	2630
lime	2890
shale	2943
lime	3297

SIM 3297 equals 3293
Total Depth.

Jet Gun 3278-3284 2000 gal acid. 8-14-40
3280-3284 6 qts. 8-15-40
Jet Gun 800 and 1700 gal acid. pressure treatment.
2000 gal under 1400# pressure 8-23-40
2000 gal acid 8-27-40