


Company - ATLANTIC REFG. CO.
Farm - Matosh "B" No. 2.

34-16-10W
SEC. 34 T. 16 R. 10 W
SE SW NE

Total Depth. 3272'
Comm. 8-13-44 Comp. 9-4-44
Shot or Treated.
Contractor. Simpson & Noble, Inc.
Issued. 9-30-44

County. Ellsworth
KANSAS



CASING:
8 5/8" 372' Cem.
5 1/2" 3266' Cem.

Elevation. _____

Production. Pot. 307 B.
plus 19% wtr

Figures indicate Bottom of Formations.

clay & sand	0-150
shale & shells	383
shale	565
anhydrite lime	575
anhydrite	600
shale & shells	1225
salt	1330
shale & shells	1520
lime sdy	1662
shale & lime	1774
shale & lime shells	1813
lime brkn	1857
shale	2025
shale & shells	2235
lime & shale	2378
shale	2490
shale & shells	2580
shale	2640
lime	2854
shale	2929
lime	3210
shale	3233
lime	3272

Total Depth.

Producing Area 3266-72

Acidized w/500 gals.
Re-acidized w/1000 gals.
Re-acidized w/1500 gals.

Tops: Lansing 2952
Arbuckle 3265