

34-16-10W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HERNDON DRILLING CO.
Farm - Phillips No. 6

SEC. 34 T. 16 R. 10W
NW SE SW

Total Depth. 3291'

Comm. 2-5-47

Comp. 2-16-47


Shot or Treated.

Contractor.

Issued. 4-5-47

County. Ellsworth

KANSAS



Elevation. 1810m

Production. Phy. 461 bbls.

CASING:

8-5/8" 356' Cem. w/250 sx

5-1/2" OD 3246' Cem. w/200 sx

Figures Indicate Bottom of Formations.

rigging up surface	0-45
shale & shells	356
red bed	570
shale	590
anhydrite	620
shale & salt	1020
shale & shells	1280
shells	1325
shale & shells	1640
lime	1825
lime & shale	2060
shale	2350
shale & lime	2650
lime	3080
lime & shale	3126
lime break	3138
lime	3247
Arbuckle	3250
lime	3291
Total Depth	

Tops:

Lansing-K.C. Lime 2945

Arbuckle Dolomite 3244