

34-16-10W

CITIES SERVICE OIL CO.  
Schroeder "C" No. 1.

SEC.34 T.16 R. 10 W  
CNL NE NW  
330'S 660'W N $\frac{1}{2}$  Cor.

Total Depth. 3307'  
Comm. 9-23-41 Comp. 10-13-41  
Shot or Treated.  
Contractor. Hisson Drlg.Co.  
Issued. 12-13-41

County. Ellsworth



CASING:  
8 5/8" 335' Cem.  
5 1/2" 3286' Cem.

Elevation.

Production. Phy.Pot.292 B.  
no wtr

Figures Indicate Bottom of Formations.

clay & shale	0-123
shale, lime, iron	335
shale & red bed	650
shale	995
shale & lime shells	1038
shale & salt	1290
lime & shale	1325
lime	1461
shale & lime shells	1633
lime brkn	1740
lime	1810
shale & lime shells	2059
lime & shale	2203
lime	2300
shale & lime shells	2435
lime & shale	2550
lime	2882
shale	2945
lime	3075
shale	3084
lime	3287
3287 Rot.TD=3290 SLM	
dolomite	3307
Total Depth.	

Corr. Top Arbuckle 3285  
Penetration 22

500 Gals. Acid 10-15-41  
2500 Gals. Acid 10-18-41

1 $\frac{1}{2}$  BOPH at 3307