

34-16-10W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL COMPANY
Farm - Schroeder "C" No. 5

SEC. 34 T. 16 R. 10W
CS 1 NW
330' N & 1300' W of Center

Total Depth. 3290'

Comm. 3-22-47 Comp. 4-9-47
Shot or Treated. Acid. w/500 gals. 4-14-47
Contractor. Corbott-Barbour Drilling Co.
Issued. 7-12-47

County. Ellsworth
KANSAS



CASING:

8-5/8" 321' Cem. w/150 sx
5-1/2" 3270' Cem. w/100 sx

Elevation. 1818 *act & rh.*

Production. Phy. Pot: 137 BO, 4BW,
24 hrs.

Figures Indicate Bottom of Formations.

surfaced clay	0-40
shale	92
sand	155
shale & shells	592
anhydrite	620
shale & shells	1345
anhydrite	1420
shale & shells	1430
lime sdy & shale	1545
shale & lime	1640
lime	1705
limo & shale	1935
lime brkn	2000
limo & shale	2165
shale	2290
shale & limo shells	2420
shale & shells	2495
limo " shale	2585
limo	2960
limo & shale	2995
lime	3025
shale & lime	3086
lime	3210
limo & shale	3244
lime	3271
3271 RTD= 3272 SIM	
lime	3290
Total Depth	

Tops:

Lansing 2954
Eros. Arbucklo corr. 3264
Arbucklo corr. 3269
Penetration 21

2 bailers (1½ bbls) in 1¼
hrs. 360' oil in 3 hrs.
Bailed 8½ BO in 2 hrs. &
lowered from 360-335'.