

OCT 18-1969

Geol. 63 6M 6-50-R

34-16-10W

# WELL RECORD

Company Cities Service Oil Co. Well No. 7 Farm Schroeder "C"  
 Location 1370' FNL & 1320' FWL Sec. 34 T. 16S R. 10W  
1821' GL  
 Elevation 1826'KB, 1823'DF County Ellsworth State Kansas  
 Initial Prod. -- Dry Hole -- P&A 8-18-69 Contractor Gabbert-Jones, Inc.  
 Acid None Drlg. Comm. Aug. 9, 1969  
 T.D. 3394' (Elec. Log TD) Drlg. Comp. Aug. 18, 1969

### CASING RECORD:

9-5/8" set @ 304' with 275 sx

### FORMATION RECORD:

surface & shale	0-310'
shale - redbed	595
anhydrite	620
shale & shells	1344
lime & shale	2275
lime	2815
lime & shale	3090
lime	3394 TD

### DRILL STEM TESTS:

- Test #1 - 3260-76 (16') Arb., 15-30-75-30  
 fair to good blow, rec. 240' gas  
 in DP, 40' oil, 170' muddy oil,  
 420' oil cut water; IFP 46#, FFP  
 293#, ISIP 873#, FSIP 732.
- Test #2 - 3285-3300' (15') Arb. 15-30-45-30  
 Strong to fair blow, rec. 2085'  
 slightly oil cut mud & water;  
 IFP 183#, FFP 979#, ISIP 952#,  
 FSIP 970#.
- Test #3 - 3301-20' (19') Arb. 15-30-45-30  
 good to fair blow, rec. 1667' muddy  
 water; IFP 105#, ISIP 1043#,  
 FFP 759#, FSIP 1025#.

### ELECTRIC LOG TOPS:

Heebner	2844' (-1018)
Brown Lime	2950' (+1124)
Lansing-Kans. City	2966' (-1140)
Base Lansing-Kans. City	3239' (-1413)
Arbuckle	3260' (-1434)

P&A 8-18-69

### Slope Tests:

500', 1/2°  
 1342', 3/4°  
 1640', 1/2°  
 1943', 3/4°  
 2680', 3/4°  
 2974', 1/2°



15-05-2 200 10  
**34-16-10W**

COMPANY Fell & Wolfe Oil Co.

SEC. 34 T. 16S R. 10W  
LOC. 50' S of C-NW/4

FARM Schroeder "C" NO. 7

COUNTY Ellsworth

ROTARY TOTAL DEPTH 3,396'  
COMM. October 11, 1979 COMP. October 13, 1979  
CONTRACTOR H-30, INC. (Rig #2)  
ISSUED October 24, 1979

CASING  
9 5/8" Set at 304' w/275 sxs by prior operator (Cities Serv. Oil)  
10 3/4"

ELEVATION 1,826' K.B.

8 5/8"

5 1/2"

4 1/2" Set at 3,394' cemented w/150 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Old Rotary Total Depth 3,394'

Washdown to 3,396'

New Rotary Total Depth 3,396'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

Merle Britting  
Merle Britting

State of Kansas }  
County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 24th day of  
October, 1979.

Elsie Willison  
Elsie Willison - Notary Public

My Commission Expires: