

35-16-10W *Plotted A&C.*


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

LARIO OIL & GAS CO.
Mitcheal Mehl No. 7.

SEC. 35 T. 16 R. 10W
CW $\frac{1}{2}$ NE SE

Total Depth. 3309'
Comm. 10-25-40 Comp. 11-14-40
Shot or Treated.
Contractor.
Issued. 12-7-40

County. Ellsworth



CASING:
8 " 174'
5 $\frac{1}{2}$ " 3306'

Elevation.

Production. Pot. 2447 B.

Figures Indicate Bottom of Formations.

surface clay	60
sand	90
shale	174
red bed & shells	300
shale blue	450
red bed	600
anhydrite	627
shale	830
lime brkn	890
shale & shells	925
lime	960
shale & shells	1040
shale	1180
lime brkn sdy	1305
shale	1327
lime	1595
sand	1650
lime	2115
shale	2140
shale & sdy lime	2230
lime brkn	2290
lime	2365
lime brkn	2490
sand hrd	2510
lime sdy	2575
lime	3187
chert & lime	3240
shale & lime	3260
shale & sand	3288
shale & dolomite	3308
lime	3309
Total Depth.	

Acid 1750 gallons
Stage Treatment
1 - 500 gallons
2 - 500 gallons
3 - 750 gallons