


SKELLY OIL COMPANY.
 Louis Meyer No. 1

SEC. 35 T. 16 R. 10W.
 CS $\frac{1}{2}$ SW NE
 330' fr SL 660' fr WL. NE $\frac{1}{4}$

Total Depth. 3300 equals 3298 SLM
 Comm. 7-26-40 Comp. 8-6-40
 Shot or Treated. No acid treatment
 Contractor. Hissom Drlg. Co.
 Issued. 10-26-40

County Ellsworth.



Rotary

CASING.

85/8" 322' Cem.
 4 1/2" 3295 SLM cem.

Elevation.

Production. Pot. 5122 B.

Figures Indicate Bottom of Formations. Echometer. Max. Pot. 3000B.

surface soil, clay, sand and shale 275
 shale and sand 322
 shale 585
 lime 625
 shale and shells 1020
 shale and salt 1301
 broken lime 1469
 lime grey 1520
 lime and shale 1640
 sand 1671
 lime 1713
 broken lime and shale 1803
 broken lime 1893
 lime 2034
 broken lime & shale 2067
 broken lime 2140
 shale and shells 2154
 shale 2284
 shale lime shells 2490
 broken lime 2692
 lime 2880
 broken lime 2992
 lime and shale 3094
 lime 3225
 broken lime 3281
 chert and shale conglomerate 3286
 shale green & little sand 3293
 brown grey sand 3295
 Medium saturation.
 dolomite grey and brown 3300
 good porosity and saturation.
 Corr. 3300 SLM rotary table equals
 3298 SLM derrick floor, which
 accounts for above Top of Arbuckle
 lime and 4 1/2 casing point.

On August 12th, POB 11 hours with
 Echometer 180 bbls of oil and no wtr
 which indicated 24 hour productivity
 of 5122 bbls to establish Max. Pot
 of 3000 bbls., This potential allows
 44 bbls per day for the remainder
 of August 1940.

Tops. - Lansing lime 2980
 Simpson shale 3284
 Simpson sand 3291
 Arbuckle lime 3293

Medium Saturation 3291-3293.
 Pay formation 3293-3298

T.D. 3300 = 3298 SLM

On August 11th, ran 2" tubing and rods
 and POB 4 1/2 hours with echometer 72 bbls
 of oil and no water which indicated
 24 hour productivity of 5000 bbls.,