

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


36-16-10W

Company - B & R DRILLING, INC.
Farm - Stratman No. 1

SEC. 36 T. 16 R. 10W
O.E. 1/2 NW 1/4
1980' FSL & 800' FWL

Total Depth. 3297
Comm. 11-2'-49 Comp. 11-6-49
Shot or treated.
Contractor.
Issued. 1-14-50

County. Ellsworth
KANSAS



CASING:
8 5/8" 243' com. w/125 sx.
5 1/2" 3295' com. w/75 sx.

Elevation. 1826 Ind.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & sand	40
clay, shale, sand	180
shale & shells	243
clay, shale	465
shale red	545
shale	925
shale, shells	975
salt & shale	1280
shale, shells	1290
anhyd.	1335
shale, lime	1430
lime	1500
Ft. Riley	1680
lime, shale	2415
shale & shells	2500
shale & shells	2610
lime	2830
shale, lime	2925
shale	2930
lime, shale	2961
lime, shale	3135
lime	3285
shale	3291
Simpson	3294
Arbuckle	3297
Total Depth	

Tops: From Geological Report	Tops:
Heabner	2823
Brown lime	2930 2930
Lansing-K.C.	2952 2952
Simpson	3264
Arbuckle dol	3294 3294

2973-2985 Oolitic lime good porosity tr. stain
3046-3076 " " " " " "
very spotted staining, fair odor
3141-3152 Partly oolitic and xyn spotted
fair porosity w/saturation, washed
good rainbow-good odor.
3294- Finely xyn mostly dense dolo. very
spotted slight porosity w/show of
free oil-faint odor.