

Gypsy #1 Kozisek,  
SE corner, 16-16S-10W.  
Elevation 1891'.

Pennsylvanian conglomerate. None. Base of Kansas City lies on top of sandy Decorah. Upper foot or more may be of Pennsylvanian age but is indistinguishable from Decorah.

Ordovician Top 3333'. Sub-sea, minus 1442'.

Decorah 3333-3363'

3333-3344 Fine sand and green shales.

3344-3353 Shales, green, maroon, yellow.

Arbuckle 3353-3385 Penetration 32' Sub-sea, minus 1462'.

3353-3359 Miller, zone 10. 800' oil in 5 hrs., 54-60'

3359-3363 Purcell, zone 3. Rose 1050' in 6 hrs., 3360-69'.

3363-3366 Purcell, zone 4.

3366-3371 Purcell, zone 5.

3371-3382 Purcell, zone 6. Oil increase, 3375-80'.

3382-3385 Purcell, zone 7.

Sub-sea of Purcell, zone 5, is minus 1475'

Correlated with Gypsy #1 and #2 Stoltenberg, 22-16S-10W.