

State Geological Survey

WICHITA BRANCH

15-009-21274

KANSAS DRILLERS LOG

S. 20 T. 16 R. 11 ^EW

API No. 15 — 009 — 21,274
County Number

Loc. C N2 N2 NE

Operator

S & K Oil Co.

County Barton

Address

Box 559 Tulsa, Oklahoma 74101

Well No.

#1

Lease Name

J. Prusa "A"

Footage Location

330' FSL

feet from (N) (S) line

1320' FWL

feet from (X) (W) line

Principal Contractor

DNB Drilling, Inc.

Geologist

R. B. Gebhart, Jr.

Spud Date

11/18/77

Total Depth

3271

P.B.T.D.


Date Completed

5/15/78

Oil Purchaser

NCRA

640 Acres



1823

Elev.: Gr.

DF 1825 KB 1828

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	32	592	Common	300	2% Gel. 3% CaCl
Production	7-7/8"	5-1/2"	14	3268	"	225	2% Gel. 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
---	---	---			
TUBING RECORD			4	Jef	3259-62
Size	Setting depth	Packer set at	4	Jef	3266-69
2-1/2"	3265'	---			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
5/18/78		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	42 bbls.	T. S. T. M. MCF	170 bbls.	---	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Used on Lease.			3259-62 & 3266-69.		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & K Oil Co. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name J. Prusa "A" Oil

S 20 T 16 R 11 ^{EX} W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.
 SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	594		
Red Bed & Shale	594	680		
Anhydrite	680	702		
Shale	702	1325		
Lime & Shale	1325	2965		
Lime	2965	3255		
Lime & Shale	3255	3276		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

 Signature
 Pet. Engr.
 Title
 6/19/78
 Date

561971

DRILLERS' LOG

S & K OIL COMPANY
No. 1 Joe Prusa 'A'
C N/2 N/2 NE Sec. 20-16S-11W
Barton Co., Kansas

Commenced: 11-18-77
Completed: 11-23-77

Surface Casing: 587' of 8-5/8"
cmtd w/300 sx common, 2% gel, 3% cc
11-18-77

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 594
Red Bed & Shale	594 - 680
Anhydrite	680 - 702
Shale	702 - 1325
Line & Shale	1325 - 2965
Lime	2965 - 3255
Line & Shale	3255 - 3276 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 28th day of November 1977.

Dorothy L. Schmidt
Dorothy L. Schmidt

DOROTHY L. SCHMIDT
Notary Public
My App. Exp. April 30, 1979