

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted - J. O. B.*

*20-16-11W*


SINCLAIR PRAIRIE OIL CO.  
Joe Prusa No. 4

SEC. 20 T. 16 R. 11W.  
SEc NE  
330' fr Sth & E lines NE $\frac{1}{4}$

Total Depth. 3298  
Comm. 9-25-39 Comp. 10-12-39  
Shot or Treated.  
Contractor. Harbar Drilling Co.  
Issued. 11-11-39

County Barton.

CASING. Rotary 3292'  
Cable 3298'



103/4" 103'  
7" 3290'

Elevation.

Production. Pot 4361 B.

Figures Indicate Bottom of Formations. Nat. No wtr Echometer.

shale and shells	190	
red bed and sand shells	395	
shale red bed	625	
shale and shells	730	
anhydrite	750	
shale and shells	1200	
salt and shale	1360	
shale	1420	
lime	1480	
shale and shells	1500	
Broken lime	1590	
shale and lime	1720	
sdv lime	1795	
shale lime shells	1845	
shale and shells	1852	
lime and shale	1900	
lime	1960	
shale lime shells	2025	
lime	2120	
shale	2140	
shale and shells	2390	
shale and lime	2485	
shale and lime shells	2595	
lime and shale	2705	
lime	2773	
sand	2780	
lime	2945	
shale	2987	odor oil and gas 3040-45
lime Top K.C. 3000'	3080	
shale and lime	3089	
lime soft	3095	show oil
lime	3185	
lime hard	3188	
lime soft	3195	
lime	3230	
shale and lime	3276	
Top Arbuckle 3290		
lime	3298	

Total Depth.