

20-16-11W
 820
 820
 Plotted Tex. S. Co.
 SEC. 20 T. 16 R. 11W
 NEc NW
 440' location

SINCLAIR PRAIRIE
 P. Schmitt No. 1.

PLUGGING BACK RECORD

Total Depth. 3310' PB 3168
 Comm. 4-11-39 Comp. 5-2-39
 Shot or Treated.
 Contractor. Harbar Drlg. Co.
 Issued. 8-2-41

County. Barton

Rotary 3301
 Cable 3310



Elevation.

CASING:
 16" 131'
 9 5/8" 3301'

Production. Pot. 213 B.

Figures Indicate Bottom of Formations.

clay & lime 40
 lime shells 70
 sand wtr 85
 lime shells 117
 shale 130
 shale & shells 560
 red rock & shells 708
 anhydrite 750
 shale & shells 1130
 shale 1165
 salt 1317
 salt & shale 1425
 shale 1432
 shale & shells 1600
 shale sticky 1619
 brkn lime 1740
 shale & sand 1762
 shale, lime, sand, shells 1803
 lime 1833
 lime brkn 1880
 shale 1895
 brkn lime & shale 2020
 shale, lime shells 2062
 shale & shells 2360
 shale & lime 2464
 shale 2550
 shale & lime 2620
 lime 2630
 lime brkn 2640
 shale sticky 2645
 shale & shells 2690
 lime 2700
 lime brkn 2768
 oil show 2835-51
 lime 2925
 lime brkn & shale 2940
 sh oil or gas 2850-70
 shale 2947
 lime brkn 2960
 lime 3023
 shale 3027
 lime 3055
 lime brkn 3062

Top Kansas City 2975
 Top Conglomerate 3277
 Top Weathered Quartzite 3297
 Top Arbuckle 3304

PLUGGING BACK RECORD

Comm. 1-13-41
 Comp. 2-7-41
 Production. Pot. 4023 B.

Set 9 5/8" plug 3286-90
 Perf. 92 shots 3168-78

2000 Gals. Acid in K.C.

Plugged T.D. 3168

lime 3211
 sh oil 3070-3115
 sh oil 3170-80
 sh oil 3185-90
 lime brkn 3215
 lime 3277
 cherty lime 3279
 conglomerate 3297
 lime 3310
 Total Depth.

sh oil 3297-3302
 oil pay 3306-10