

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

20-16-11W

SINCLAIR PRAIRIE OIL CO.
Peter Schmitt No. 3.

SEC. 20 T. 16 R. 11 W
NE SE NW
330' f EL 990' f SL NW $\frac{1}{4}$

Total Depth. 3345'
Comm. 8-23-42 Comp. 9-10-42
Shot or Treated.
Contractor. Harbar Drlg Co.
Issued. 2-6-43

County. Barton



CASING:
8 5/8" 306' Cem.
5 1/2" 3345' Cem.

Elevation.

Production. Pot. 52 BO, 5BW

Figures Indicate Bottom of Formations.

sand hrd & shells	48
lime shells & shale	313
shale & shells	515
red bed	700
anhydrite	750
shale & shells	960
lime brkn	1070
shale	1145
shale & shells	1370
sand hd	1395
lime	1425
lime & shale	1690
lime sdy	1700
sand	1724
lime	1730
lime sdy	1795
lime & shale	1855
lime sdy	1880
lime shells & hd sand	1905
lime sdy	1908
chert & lime	1917
lime	1940
lime & shale	2015
lime	2120
lime & shale	2180
lime brkn	2220
lime & shale	2310
lime	2315
brkn lime & shale	2390
lime brkn	2410
shale	2435
lime	2475
shale	2500
lime & shale	2565
shale	2590
lime & shale	2615
lime hd	2635
shale & shells	2660
lime & shale	2705
lime brkn & shells	2755
lime	2925
lime & shale	2965
lime sft-slight odor	2985

Tops:
K. C. 3005
Conglomerate 3202
Reworked lime 3297
Arbuckle lime 3345
5 1/2" set at 3345' left
15' cement in pipe
which was not drld mak-
ing T.D. 3330
Production is from
lower K.C. lime
Acidized 1000 Gals.
thru perforations
3292-97 in lower K.C.

lime & shale	3020
lime rough	3080
lime	3086
lime sft brown-odor	3135
lime hd	3140
lime	3160
sand	3167
lime	3175
shale	3205
shale & lime	3292
lime sdy	3306
conglomerate & chert	3345
Total Depth.	