

30-16-11W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY TOM KAT, INC.

SEC. 30 T. 16 R. 11W

FARM Krier "f" A NO. 10

LOC. NW SE SE SE

TOTAL DEPTH 3302'

COMM. 7-10-66

COMP. 7-16-66

SHOT OR TREATED

CONTRACTOR Tom Kat Inc

ISSUED 5-20-67

COUNTY Barton

KANSAS

CASING

20 10
15 8 5/8" 265' cem w/ 145 sx
12 6
13 5

ELEVATION 1919' KB

PRODUCTION DRY (Gor sd)

FIGURES INDICATE BOTTOM OF FORMATIONS

0	90	Soil & Postrock	Set 265' of 8-5/8" surf.
90	110	Shale	casing with 145 sacks cement.
110	185	Shale	
185	210	Sand - Shale	TOPS:
210	265	Shale	
265	550	Shale & Sand	Heebner 2935
550	756	Red Bed	Toronto 2952
756	777	Anhydrite	Douglas 2963
777	1005	Shale & Shells	Douglas Sand 2980-89
1005	1443	Shale & Shells	Brown Lime 3032
1443	1521	Lime	Lansing 3051 (-1132)
1521	1735	Lime & Shale	
1735	1910	Lime & Shale	
1910	2195	Shale & Lime	SCOUT TOPS:
2195	2483	Shale & Lime	Anhydrite (s) 756
2483	2710	Shale & Lime	Howard 2610
2710	2815	Lime & Shale	Severy shale 2634
2815	2930	Lime & Shale	Topeka 2646
2930	3060	Lime & Shale	Queen Hill 2847
3060	3135	Lime	Heebner 2934
3135	3230	Lime	Toronto 2951
3230	3280	Lime & Shale	Douglas 2962
3280	3302	Lime & Sand	Brown lime 3031
	3302	Rotary Total Depth	Lansing 3051
			Base Kansas City 3249
			Gorham sand 3293

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Don G. Calvin
DON G. CALVIN

STATE OF KANSAS)
) SS