

31-16-11W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - NAT'L. COOP. REEG. ASS'N.  
Farm - F. D. Zorn' No. 1

SEC. 31 T. 16 R. 11W  
NE NE SW

Total Depth. 3363'

Comm. 4-4-48

Shot or Treated.


Contractor. N.C.R.A.

Issued. 4-2-49

Comp. 12-8-48 ✓

County. Barton

KANSAS



Elevation. 1899 act.

Production. Temporarily abandoned

CASING:  
12" 446' 8" 2517'  
10" 744' 7" 3230'

Figures Indicate Bottom of Formations.

cellar	10	red rock	3000
post rock & shale	25	shale	3060
shale blue	40	lime brwn	3067
shale	195	shale	3076
sand	205	lime wh	3090
shale	250	lime	3145
sand	275	shale	3155
shale	350	lime	3210
sand	420	shale	3218
shale	495	lime	3260
red rock	535	lime	3275
shale	630	shale	3285
red rock	735	lime	3307
anhydrite	750	shale	3313
lime	765	lime	3324
red rock	955	shale	3329
shale blue	995	lime sdy	3340
shale	1020	conglomerate	3357
red rock	1045	sand	3363
shale	1070	Total Depth	
red rock	1115	Water Record:	
shale	1160	HFV at 265'	
salt	1420	6" W at 540'	
shale & shells	1560	4" BW at 625'	
shale	1570	1 1/2" BW 1775'	
lime	1600	1 1/2" BW 1805-1815'	
shale	1610	1" BW 3185-3190'	
lime brkn	1670	Tops:	
shale & shells	1725	Kansas City	3055 ✓
lime	2053	Sand	3329 ✓
red rock	2063		
lime	2105		
shale & shells	2135		
lime	2140		
red rock	2145		
lime	2210		
shale & shells	2345		
lime	2360		
shale	2370		
shale & shells	2400		
shale	2420		
lime	2435		
shale	2490		
lime	2510		
shale & shells	2540		
shale	2625		
shale shells	2665		
lime	2695		
shale	2700		
lime	2815		
shale	2825		
lime	2865		
shale	2870		
lime	2965		
shale blk	2968		
lime	2975		
shale	2982		
lime	2995		