

31-16-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SKELLY OIL COMPANY
Farm- J. F. ZORN No. 6

SEC. 31 T. 16 R. 11W
C S/2 N/2 NW

990' fNL, 1320' fWL, NW $\frac{1}{4}$

County Barton
KANSAS



Total Depth. 3313 $\frac{1}{2}$ SLM; PB 3283
Comm. 9-23-53 Comp. 10-5-53

Shot or Treated.

Contractor. Claude Wentworth Drlg. Co. Inc.

Issued. 11-28-53

CASING:

8 5/8 747' cem. w/350 sx. Left in 749' 3"
5 1/2" 3254 $\frac{1}{2}$ SLM cem. w/125 sx Left in 3280'

Elevation. 1903 DF

Production. Pot. 108 bbls. oil

Figures indicate Bottom of Formations.

surface soil, shale,
shells 105
shale, shells 575
red bed, shells 650
iron, shale 740
anhydrite 768
shale, shells 770
red bed, shells 950
shale, shells 1150
shale, salt 1250
shale, shells 1495
shale, lime 2655
lime 2948
Cored 2948 - 3008
Recovered 60'
lime 3242
Quartzite 3244
Cored 3244 - 3257
Recovered 12'
Cored 3257 - 3288
Recovered 31'
Cored 3288 - 3315
Recovered 27'
Total Depth 3313 $\frac{1}{2}$ SLM DF
Plugged back to 3283

Tops:
Anhydrite 737
Topeka lime 2620
Heebner shale 2909
Toronto lime 2924
Douglas shale 2937
Douglas sand 2956
Brown lime 3006
Lansing lime 3020
Quartzite 3244

Producing formation:

Pre-Cambrian Top 3254 $\frac{1}{2}$ Bottom 3283
" 3243 " 3252

10-16-53 Shot 3254 $\frac{1}{2}$ -3286
Halliburton (Sand-Oil-Frac)

10-19-53 Shot 3243-3252
Halliburton (Sand-Oil-Frac)

TD 3315 SLM rotary table equals 3313 $\frac{1}{2}$ SLM D.F.

Oil from 2872-2880'
2952-3005'
3186-3204'
3206-3210'
3243-3283'

PE
12-2-54