

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk. Bldg., Wichita, Kansas


29-16-11W

Company GULF OIL CORP.  
 Farm Joseph No. 6.

SEC. 29 T. 16 R. 11 W  
 SW SE SW

Total Depth. 3358  
 Comm. 11-22-45 Comp. 12-20-45  
 Shot or Treated. 12-20-45 with 1000 gals.  
 Contractor.  
 Issued. 4-27-46

County. Barton  
 KANSAS



CASING.  
 8 5/8" 557' Cem.  
 5 1/2" 3351' Cem.

Elevation. 1910 rh

Production. Pot. 230 B, no wtr

Figures Indicate Bottom of Formations.

surface	100
shale shells	630
red bed	750
hard sand	790
shale & shells	1375
sand, shale & shells	1645
shale & shells	1785
sand, shale & lime	1900
sand-lime	1964
lime	2020
lime & shells	2125
lime & shale	2258
shale & shells	2505
lime & shale	2605
shale & shells	2740
shale & lime	2785
lime Rotary	3354
lime	3358
Total Depth	

Tops:

Heabner	2956
Toronto	2976
Base Oread	2991
Brown Lime	3052
Lansing	3069
Arbuckle	3350