

29-16-11W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GULF OIL CORPORATION

SEC. 29 T. 16 R. 11 W
LOC. NW NE SW

FARM Joseph

NO. 7

TOTAL DEPTH 3320'

COMM. 2-6-51


COMP. 2-28-51

SHOT OR TREATED

CONTRACTOR

ISSUED 5-5-51

COUNTY Barton
KANSAS



CASINO

8-5/8" 746' cem. w/345 sx.
5 1/2" 3317' cem. w/100 sx.

ELEVATION 1892'

PRODUCTION IPP 79 bbls. &
no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface soil & shale	215
Shale & shells	1465
Shale & lime	1825
Lime	1955
Shale & shells	2160
Shale & lime	2690
Lime	2755
Lime & shale	2800
Lime	2905
Lime & shale	2960
Lime	3320
Total Depth	

Tops:	
Heebner	2929
Toronto	2949
Brown lime	3029
Lansing	3047
Arbuckle	3316

Acidized:
With 500 gallons 2-27-51

P1

WELL LOG ON JOSEPH #7

Spudding date: 2/6/51
 Date casing set: 2/17/51
 Date rotary completed: 2/15/51
 Date cable completed:

Location:

**Center NW NE SW Sec. 29-168-11N
 Barton County, Kansas**

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	215	Surface soil and shale	
215	1465	Shale and shells	Ran 27 jts. 8-5/8" csg. at 610' w/375 ex. bulk cement
1465	1825	Shale and lime	
1825	1955	Lime	
1955	2160	Shale and shells	
2160	2690	Shale and lime	
2690	2755	Lime	
2755	2800	Lime and shale	
2800	2905	Lime	
2905	2960	Lime and shale	
2960	3320	Lime	
3320		TOTAL DEPTH	Ran 107 jts. 5 1/2" O. D. 8 thread csg. at 3317' w/100 ex. bulk cement.

APR 22 1955

State Geological Survey
 WICHITA BRANCH

RECEIVED
 STATE CORPORATION COMMISSION

APR 18 1955

CONSERVATION DIVISION
 Wichita, Kansas

29-16-11W

29-16-11W

WELL NO. 7 LEASE Joseph COMPANY Gulf Oil Corporation A.F.E. 2548

DATE—DRILLING BEGAN 2-6-51 WELL COMPLETED 2-28-51 FIRST PRODUCTION 2-26-51

SAND RECORD Top Arbuckle 3316' TOTAL DEPTH 3320'

INITIAL PRODUCTION OIL: "P" 79 Barrels
WATER: None

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8"	32	8V	C	Smls.	746'	345			746'
5-1/2"	14	8R	*	Smls.	3317'	100			3317'
*47 Jts.			Class A						
60 Jts.			Class B						

S— 29 T— 16S R— 11W

			C—		
			NW		
			NE		
			SW		
			Barton		
			County		
			Kansas		

ELEVATION— 1892'

ISTANCE H: Top collar on 5-1/2" casing to rotary bushing is 6'.

ACIDIZED: With 500 gallons 2-27-51

ACIDIZED: 5-1-53 to 5-4-53

ACIDIZED: with 500 gallons

PRODUCTION: Before "P" 9 oil 75 water

After "P" 29 oil 261 water 5-9-53

AFE 3139

APR 22 1985

State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1935

CONSERVATION DIVISION
Wichita, Kansas