

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


35-16-11W

Company- The EL DORADO REFINING COMPANY
Farm- Anna Ehler "B" No. 1

SEC. 35 T. 16 R. 11W
NE NE NW

Total Depth. 3385 RB
Comm. 6-19-52 Comp. 6-30-52
Shots Fired.
Contractor. Group Exploration Company
Issued. 8-16-52

County Barton
KANSAS



CASING:

8 5/8" 308' cem w/150 sx
5 1/2" 3390' cem w/ 50 sx

Elevation. 1931

Production. 357 bopd / trace wtr

Figures Indicate Bottom of Formations.

shale, shells	160
shale	425
sand	525
shale	630
shale, sand	740
anhydrite	775
shale	1140
shale, lime	2385
shale, shells	2515
shale	2645
lime	2725
shale	2765
lime	2985
shale, lime	3075
lime	3385
Total Depth RB	

Tops: D.F.	
Heebner	2969
Toronto	2989
Brown Lime	3070
Lansing	3085
Conglomerate	3367
Arbuckle	3378

DST: 3297-3314, op. 30 min.
rec. 60' wtr & 15' muddy wtr.
BHP 1000#.

Trace stain poor to no porosity Toronto 2989.
F.S.F.O & fair odor med. xln.
dol. sln. por. Arb. 3378

D.P. & C.O. to R.T.D., 3382 D.F.,
2 goph: D.D. 3384, $\frac{1}{2}$ boph, 500
acid. 3050' OIH static, swabbed
20 BOPH 350' O.B.

Total Depth - 3385' (w/r) R.B. 3382' D.F.
- 3384 (w/c.t.) D.F.