

22-16-11W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP.
Farm - Sophia Besthorn No. 2

SEC. 22 T. 16 R. 11 W
SWc SW

Total Depth. 3348'
Comm. 11-28-45 Comp. 1-31-46
Shot or Treated. Acidized w/2000 gals.
Contractor.
Issued. 3-23-46

County. Barton
KANSAS



CASING:

8 5/8" 549' Cem. LI 539'
5 1/2" 3343 1/2' Cem. LI 3337'

Elevation. 1921

Production. DD Pot. 1455 BO, no
wtr.

Figures Indicate Bottom of Formations.

Tops:

Heebner 2947
Douglas 2979
Brown lime 3046
Lansing 3060
Base Kansas City 3337
PBC 3340
Arbuckle 3342

clay	0-35
limestone	50
shale	65
limestone & shale	220
shale & shells	275
sand & shells	330
shale & shells	415
red bed & shells	445
shale & shells	475
shale sdy	504
pyrite	510
shale	512
sandstone, shale & sand	550
red bed & shale	590
red bed & shells	750
shale, sticky	780
red bed, shells & shale	975
red bed & shells	1115
shale & shells	1300
salt, shale & shells	1480
shale & shells	1590
shale lime	1695
shale & shells	1795
lime brkn & shale	1875
lime	1944
lime brkn	2030
lime brkn & shale	2201
lime & shale	2492
shale & lime brkn	2655
lime brkn	2700
lime & shale	3107
lime	3348
Total Depth.	

Acidized w/2000 gals. 1-30-46
Arbuckle lime 3342-48'