


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg. Wichita, Kansas.

SINCLAIR PRAIRIE OIL CO.
Chas. O. Davidson No. 2

SEC. 4 T. 16 T. 11W.
NW SE SE
990' fr E. and S.L. SE $\frac{1}{4}$

Total Depth. 3356
Comm. 2-1-37 Comp. 3-14-37
Shot or Treated.
Contractor.
Issued. 6-5-37

County Barton.



CASING.

15 $\frac{1}{2}$ " 297' 7" 3314'
2" tubing.

Elevation.

Figures Indicate Bottom of Formations.

Production. Pot. 150 B.
12 B.W. after
shot.

lime and shale	85	
lime	90	
sand and lime	297	
shale and lime	343	
sand	485	
shale and shells	500	
shale sticky	596	
shale and red bed	714	
anhydrite	735	
shale and shells	1390	
lime	1685	
limewith iron	1760	
lime	1885	
lime with iron	1894	
lime	1921	
shale and shells	1956	
shale and lime	2179	
shale	2234	
broken lime	2256	
shale and shells	2380	
lime	2414	
shale lime and shells	2451	
shale	2465	
lime	2529	
shale and shells	2575	
lime hard	2583	
shale	2610	
lime hard	2620	
shale	2624	
lime	2664	
lime broken	2707	
shale and lime	2747	
shale and shells	2804	
lime	3000	
lime K.C.	3030	Top K.C. 2991 Base 3308
lime	3064	show oil in cuttings.
lime K.C.	3137	
lime broken	3173	
lime K.C.	3267	
lime broken	3296	
lime K.C.	3317	
conglomerate and sand	3356	
Total Depth.		
Top conglomerate	3316	
best oil in	3320-30	