

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

ISERN BROS. ET AL.
Lillard No. 1.

SEC. 6 T. 16 R. 11W.
CWL SW SE

Total Depth. 3278
Comm. 1-19-41 Comp. 3-5-41
Shot or Treated.
Contractor. Sharon Drilling Co.
Issued. 4-5-41

County Barton.



CASING.

8 $\frac{1}{4}$ " 63'
4 $\frac{1}{2}$ " 3272'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

shale	63
shale and shells	300
sand	370
shale and shells	490
red rock	686
anhydrite	720
red rock and shells	990
shale and shells	1120
shale and salt	1345
anhydrite and shale	1420
lime and shale	1475
broken lime	1575
lime and shale	1690
sand	1750
shale	1765
lime and shale	1920
lime	1945
broken lime	2090
shale	2265
shale and shells	2355
lime	2380
lime and shale	2600
shale	2627
lime	2690
broken lime and shale	2740
lime	2895
shale	2955
lime brown Dodge	2960
shale	2968
lime	3059 Lansing.
lime Porous	3072
lime	3258
sand	3260
sdv shale and chert - core	3265
sdv shale & chert	3268
shale green	3271
Arbuckle Dolomite	3278
Total Depth.	

TOPS -

Anhydrite	686
Ft. Riley	1615
Topeka	2605
Chert zone in Topeka	2640-50
Dodge brown lime	2955-60
Lansing	2968
Chert Congl.	3255
Congl. sand sh oil	3258-60
Arbuckle	3271
Oil stain	3273-76 $\frac{1}{2}$
Drilled plug - trace free oil	
1000 acid.	
750' Fluid 1 hour	
1100' Fluid 2 hours	
Swabbed at rate 12 bbls Fluid per hr	
Approximately 4 bbls oil, 8 bbls water per hour.	
Halliburton squeeze job 3376 $\frac{1}{2}$, well made all water and no oil.	
Acid.	
1000 gal	
500 gal	
1000 gal	