

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock Wichita, Kansas

Company - TRANSIT CORPORATION & J. M. HUBER CORP.  
Farm - Laudick No. 1

SEC. 6 T. 16 R. 11W  
SW SW NE

Total Depth. 3395  
Comm. 4-26-50 Comp. 5-10-50  
Shot or Treated.  
Contractor.  
Issued. 6-3-50

County. Barton  
KANSAS



CASING:  
8 5/8" 550' cem. w/300 sx

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

clay & shells	60
sand & clay	90
sand & shells	158
shale	195
sand	210
shale	345
iron & sand	400
sand & shale	430
iron & hard sand	455
redbed & shale	578
redbed & shells	735
anhydrite	760
redbed & shale	990
shale	1210
salt & shale	1275
shale & shells	1390
broken lime	1470
lime	1560
lime & shale	2520
shale & shells	2450
lime & shale	2715
broken lime	2745
lime	2940
lime & shale	3010
lime	3295
lime & shale	3330
conglomerate & sand	3360
sand & shale	3395
(No casing set)	
Total depth	

Tops:	
Anhyd.	735-60
Topeka	2640 ?
Heebner	2918
Brown lime	3005
L.K.C.	3025
Congl.	3321
Arb.	3341-60

D.S.T. 2864-75 open 1 hr. rec. 60' salt wtr.  
D.S.T. 3053-61 open 35 min. dead all way thro.  
D.S.T. 3343-60 rec 120' O.C.M. Rec. 120' blk sulphur wtr.