


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WOODMAN & IANNITTI, et al
Farm- Woydziak No. 1

SEC. 6 T. 16 R. 11W
CS/2 SW SW

Total Depth. 3330
Comm. 11-23-56 Comp. 12-3-56
Shot or Treated.
Contractor. Woodman & Iannitti Drlg Co.
Issued. 12-29-56

County Barton
KANSAS



CASING:
8 5/8" 308' cem.w/150 sx.

Elevation. 1872 RB

Production. Dry

Figures Indicate Bottom of Formations.

s. soil, rock	42
shale, shells	60
sand	76
shale, shells	400
sand	440
iron pyrite	465
red bed, shale	715
iron	745
anhydrite	770
red bed, shale	974
shale, shells	1095
shale, shells, salt	1335
shale, shells	1785
lime brown, shale	1860
lime, shale	2264
shale, shells	2450
shale, lime shells	2615
shale, lime	2660
lime	2725
lime, shale	2910
lime	2957
shale, lime shells	2995
shale, lime, shells	3060
lime	3280
lime, shale	3325
Arbuckle	3330
Total Depth	

Tops:
Anhydrite (driller) 765
Heebner 2926
Dodge 2947
Brown lime 3018
Lansing 3034
Arbuckle 3314

Drill Stem Test: 3315-20.
After pulling this test it
was found out that the tool
had plugged.

Another DST was taken from
3316-25. Tool open 1 hr w/
good blow throughout. Rec.
120' oil & gas cut mud w/20
min. BHP 75#.

Another DST was taken from
3321-30, with the test open
1 hr & a good blow throughout.
Rec. 120' slightly O & GCM &
120' slightly gas cut mud,
60' water mud & 120' salt water.
a 20 min. BHP showed 1125# with
IFP 200# & FFP 400#