


GULF OIL CORPORATION.
 V. Staudinger No. 1

Sec. 7 T. 16 R. 11 W
 CSE SE

Total Depth. 3291
 Comm. 3-29-42 Comp. 4-16-42
 Shot or Treated. 1000 gal acid 4-16-42
 Contractor.
 Issued. 5-30-42

County Barton.



CASING.

85/8" 324' LI. Cemented.
 5 1/2" 3285' LI. Cemented.

Elevation.

Production. Pot. 277 B.

Figures Indicate Bottom of Formations. No wtr.

cellar	11	Topeka lime	2866
surface rock and clay	30	lime	3028
shale and shells	240	K.C. lime	3089
red shale and shells	315	lime	3128
shale and shells	339	K.C. lime	3148
shale	640	lime	3178
red bed and shale	700	lime cored	3182
anhydrite	730	lime	3196
shale and shells	800	K.C. lime	3241
lime	815	lime	3279
shale and lime	905	conglomerate	3284
shale and shells	1100	Arbuckle lime	3291
shale and salt	1300		
shale and shells	1395	Total Depth.	
lime	1490		
broken lime and shale	1500		
anhydrite and lime	1560	Arbuckle lime 3284-3291	
shale and shells	1600		
shale and lime shells	1710		
broken lime	1755		
lime	1860		
broken lime	2020		
lime	2058		
broken lime	2110		
shale and lime shells	2155		
shale and shells	2275		
lime	2290		
broken lime and shale	2372		
shale and shells	2590		
lime	2680		
Topeka lime	2734		
lime	2841		