


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
 Farm - Ney No. 3

SEC. 8 T. 16 R. 11W
 CS $\frac{1}{2}$ SW SW
 330' N & 660' E. of SW cor.

Total Depth. 3297
 Comm. 5-21-50 Comp. 6-7-50
 Shot or Treated. 500 gals. Acid
 Contractor. Lohmann-Johnson Drlg.
 Issued. 7-29-50

County. Barton
 KANSAS



Elevation. 1863'

Production. Phys. Pot. 119 oil
 6 wtr.

CASING:

8 5/8" 320' cem. w/200 sx.
 5 1/2" 3288' cem. w/150 sx.

Figures Indicate Bottom of Formations.

surface soil	40
shale & shells	323
shale & redbed	710
shale & shells	980
shale	1335
lime brkn	1760
lime	1976
lime brkn	2425
lime	2490
lime brkn	2620
lime & shale	2772
lime	2895
lime & shale	2990
lime	3290
3290 RTD = 3291 SLM	
lime	3297
Total Depth	

Tops: Corr.	
Topeka	2664
Wansing	3014
Arbuckle	3287

Pen. 10'

Fillup:

270' oil in 2 hrs. 25 mins. at 3291
310' " " 3 " 25 " " 3291
585' " " 5 " 25 " " 3294
800' " " 6 " 25 " " 3294
860' " " 8 " 25 " " 3294
910' " " 9 " 25 " " 3294
1100' " " 12 " 25 " " 3297
1240' " " 13 " 25 " " 3297