


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARBAR & GLOBE  
Farm - Redetzke No. 1

SEC. 16 T. 16 R. 11W  
SW SE SW

Total Depth. 3329  
Comm. 11-22-45 Comp. 12-20-45  
Shot or Treated.  
Contractor.  
Issued. 9-14-46

County. Barton  
KANSAS



CASING:  
10 3/4" 347' Cem.

Elevation.....  
Production. Dry

Figures Indicate Bottom of Formations.

surface dirt	40
sand	65
shale & shells	175
sand	200
shale & shells	300
sand	345
shale & shells	370
shale	390
shale & shells	500
red bed	700
shale	725
shale	935
shale & shells	1520
shale & lime	1585
lime	2100
B. lime shale	2150
shale	2230
shale & shells	2340
lime	2375
shale	2395
shale & lime	2450
lime	2495
lime, shale & shells	2565
lime	2620
shale & shells	2645
lime	2995
KC Lime	3020
lime	3275
Conglomerate dirt	3318
lime	3325
Arbuckle	3329
Total Depth	

enstalled at 36' and cemented  
with 15 sacks of Cem. from 36' to  
6' bottom of cellar.

Tops:

Lansing brown	2960
Lansing wht	2996
Lgt. Por & stain	2996-3000
Good odor & fair sat.	3004-10
Good Por.	3023-31
Good Por. no shows	3092-3111
Good Por. & sat.	3170-84
Base KC	3276
Arbuckle	3311

Hole filled with heavy mud  
from 3329 to 347  
Permanent plug placed at 347  
and cemented with 20 sks of cem.  
Hole filled with heavy mud from  
307 to 36 and permaneno plug