

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - SINCLAIR OIL & GAS CO.
Farm - Martha Oeser- No. 5

SEC. 17 T. 16 R. 11W
NE SE SW

Total Depth. 3278 PB 3256
Comm. 5-29-51 Comp. 6-10-51
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 7-28-51

County. Barton
KANSAS



CASING:
8 5/8" 28 1/2' cem. w/200 sx
5 1/2" 3271-1/2' cem. w/500 sx

Elevation. 1882 rig flr.
Pot.
Production. 237 bbls.

Figures Indicate Bottom of Formations.

surface soils, shale,	
shells	28 1/2
shale, sand, shells	46 1/2
gry lime	469
sand, hrd	499
shale & shells	709
iron & sand hrd	72 1/2
shale & shells	81 1/2
red bed, shale, shells	120 1/2
red bed shale, shells,	
salt	136 1/2
anhydrite, red bed,	
shale	146 1/2
lime, shale, shells, red-	
bed	157 1/2
lime, shale	178 1/2
lime	2039
lime & shale	2359
shale, shells	244 1/2
lime	2500
lime, shale, sand	2607
lime, shale	2738
lime hrd	2748
lime sft	2752
lime broken	2772
lime & shale	28 1/2
lime, broken sft	2960
lime	3071
lime, med	3116
lime hrd	3120
lime	3272
lime	3278
Total Depth PB 3256	

Tops:
Topeka 2647
Heebner 2889
Dodge 2905
Lansing-Kansas City 2999
Quartzite-Pre-Cambrian 3271

Ran Schlumberger @ 3272'
Perf. Kansas City 48 holes
3244-3252' lgt oil show
Acidized with 1000 gals. no inc.
Perf. 46 holes 3211-3224' show
oil, acidized 3000 gals. after
acid load out swabbed 67 bbls.
oil, no wtr.
6-18-51 state test pumped 79 bbls.
oil, no wtr in 8 hrs. for pot.
of 237 bbls.